

Europäisches Patentamt

European Patent Office

Office européen des brevets



(11) EP 1 182 173 A1

(12)

## **EUROPEAN PATENT APPLICATION**

(43) Date of publication: 27.02.2002 Bulletin 2002/09

(51) Int Cl.7: C03B 37/012

(21) Application number: 01301471,7

(22) Date of filing: 19.02.2001

(84) Designated Contracting States:

AT BE CH CY DE DK ES FI FR GB GR IE IT LI LU

MC NL PT SE TR

Designated Extension States: AL LT LV MK RO SI

(30) Priority: 08.08.2000 US 644603

(71) Applicant: LUCENT TECHNOLOGIES INC. Murray Hill, New Jersey 07974-0636 (US) (72) Inventors:

Dong, Xiaoyuan
 Suwanee, Georgia, 30024 (US)

 Hong, Siu-Ping Alpharetta, Georgia, 30022 (US)

(74) Representative:

Watts, Christopher Malcolm Kelway, Dr. et al Lucent Technologies (UK) Ltd, 5 Mornington Road

Woodford Green Essex IG8 OTU (GB)

# (54) Preform for optical fibres and methods for making the preform and optical fibres

(57)Disclosed is a preform and a method of its manufacture and a method of making optical fiber from the preform. The method includes the steps of providing an overclad tube (54), positioning a plurality of preform core rods (52) in the overclad tube end-to-end, and heating the overclad tube and the plurality of preform core rods to collapse the overclad tube onto the plurality of preform core rods to form an overclad optical fiber preform. In this manner, the interfaces between the ends of the stacked preform core rods tend to be, for example, less than approximately 1 millimiter (mm). Once the plurality of preform core rods are stacked within the overclad tube, one of the ends (58) of the overclad tube is sealed and a pressure gradient or vacuum is established across the overclad tube. In the presence of the pressure gradient, heat is provided to the combined overclad tube and preform core rods to collapse the overclad tube onto the preform core rods to form a preform. From this preform, optical fiber is drawn, for example, in a conventional manner.




FIG 2

10

30

40

### Description

### **Background of the Invention**

### 1. Field of the Invention

[0001] The invention relates to methods and apparatus for making optical fiber preforms. More particularly, the invention relates to Rod-In-Tube (RTT) methods and apparatus for making optical fiber preforms using multiple preform core rods.

1

#### 2. Description of the Related Art

[0002] Optical fibers typically are fabricated by heating and drawing a portion of an optical preform comprising a refractive core surrounded by a protective glass cladding. Conventionally, several processes exist for fabricating preforms, including a modified chemical vapor deposition (MCVD) process. See, for example, U.S. Pat. No. 4,217,027, which is issued to MacChesney et al. on Aug. 12, 1980 and co-owned with this application. Another conventional process for fabricating preforms is the vapor axial deposition (VAD) process.

[0003] In the MCVD process, precursor gases such as SiCl<sub>4</sub> and GeCl<sub>4</sub> pass through a rotating substrate tube of silica glass. A torch heats the tube from the outside as the precursor gases pass therethrough, causing deposition of submicron-sized glass particles on the inside surface of the tube. Movement of the torch along the longitudinal axis of the tube in a plurality of passes builds up layer upon layer of glass to provide a preform tube. Once a suitable number of layers have been deposited, the preform tube is heated to cause it to collapse into a solid rod typically referred to as the core rod, the preform core rod, or the preform rod.

[0004] The preform core rod then is inserted into a glass overclad tube, which is collapsed onto the preform core rod using heat and a pressure gradient present about the overclad tube to produce an overclad preform. Such process typically is referred to as the Rod-In-Tube (RIT) process. See, for example, US 4,820,322, which is co-owned with this application.

[0005] The overclad tube is collapsed onto the preform core rod while the overclad tube and the preform core rod are mounted in a vertical lathe. Alternatively, according to the Overclad During Draw (ODD) technique, collapse of the overclad tube onto the preform core rod occurs in the draw tower furnace, which also is used to draw optical fiber from the resulting optical fiber preform. In this manner, the overclad tube is collapsed progressively onto the preform core rod just prior to the resulting preform portion having optical fiber drawn therefrom.

[0006] Typically, the size of overclad preforms made by RIT processes are determined by, for example, the size of equipment used to manufacture the preform core rods and/or the overclad tubes. However, increasing the

length of the overclad preform is one manner in which to increase the yield of optical fiber drawn from the overclad preform. Because of such potential yield increase. the lathes used to rotate the substrate tubes have been made longer to manufacture preform core rods having greater length. The longer preform core rods are, in turn, used to make overclad preforms having greater length, which preforms yield more optical fiber per preform. However, limitations in MCVD processes, for example, gas flow limitations, effectively limit the overall length of preforms that are manufactured by MCVD processes. [0007] Therefore, conventionally, overclad preforms are made longer by joining overclad preforms end-toend. Such methods involve cutting, grinding, polishing and cleaning the ends of the overclad preforms to be joined. The ends are then spliced together using, for example, conventional techniques. However, the resulting splice joints between joined preforms typically are undesirably rough and distorted. Such a splice joint represents a relatively large portion (for example, greater than approximately 2 centimeters) of distorted preform glass that tends to produce reduced quality optical fiber when that portion of the preform is drawn. Often those portions of the optical fiber drawn from the preform splice joint regions must be discarded.

[0008] Accordingly, what is desired are methods and apparatus for manufacturing optical fiber overclad preforms that are longer, but do not generate as much reduced quality fiber as conventional techniques.

#### Summary of the Invention

[0009] The invention is as defined by the claims. Embodiments of the invention include a method and apparatus for making an optical fiber preform and for making optical fiber from the preform. The method includes the steps of providing an overclad tube, positioning a plurality of preform core rods in the overclad tube, and heating the overclad tube and the plurality of preform core rods to collapse the overclad tube onto the plurality of preform core rods to form an overclad optical fiber preform. According to embodiments of the invention, the plurality of preform core rods are stacked, for example, end-to-end, within the overclad tube. In this manner, the interfaces between the ends of the stacked preform core rods tend to be, for example, less than approximately 1 millimeter (mm). Once the plurality of preform core rods are stacked within the overclad tube, one of the ends of the overclad tube is sealed and a pressure gradient or vacuum is established across the overclad tube. In the presence of the pressure gradient, heat is provided to the combined overclad tube and preform core rods to collapse the overclad tube onto the preform core rods to form a preform. From this preform, optical fiber is drawn, for example, is a conventional manner.

#### **Brief Description of the Drawings**

[0010] In the drawings:

Fig. 1 is a cross-sectional view of a conventional preform core rod positioned within an overclad tube prior to progressively collapsing the overclad tube around the preform core rod to make an overclad preform;

Fig. 2 is a cross-sectional view of a plurality of preform core rods stacked and sealed within an overclad tube prior to collapsing the overclad tube therearound to make an overclad preform according to embodiments of the invention;

Fig. 3 is a cross-sectional view of a plurality of preform core rods stacked within an overclad tube prior to collapsing the overclad tube therearound to make an overclad preform according to an alternative embodiment of the invention; and

Fig. 4 is a simplified block diagram of a method for making overclad optical fiber preforms using multiple preform core rods, and making optical fiber therefrom according to embodiments of the invention.

#### **Detailed Description**

[0011] In the following description similar components are referred to by the same reference numeral in order to enhance the understanding of the invention through the description of the drawings. Also, although specific features, configurations and arrangements are discussed hereinbelow, it should be understood that such is done for illustrative purposes only. A person skilled in the relevant art will recognize that other steps, configurations and arrangements are useful without departing from the spirit and scope of the invention.

[0012] Referring now to Fig. 1, illustrated is an apparatus 10, comprising a preform core rod 12 and an overclad tube 14, used to make an overclad preform, for example, according to a conventional Rod-In-Tube (RIT) process. The preform core rod 12 is positioned within the overclad tube 14 prior to the collapse of the overclad tube 14 around the preform core rod 12.

[0013] The preform core rod 12 is made by any suitable process, including conventional processes such as modified chemical vapor deposition (MCVD) or vapor axial deposition (VAD). The preform core rod 12 has a proximal end 22 and a distal end 24, and often is made with a handle 26 at the proximal end 22. The handle 26 facilitates maneuvering the preform core rod 12 into the overclad tube 14.

[0014] The overclad tube 14 has a first end 32 into which the preform core rod 12 is inserted and a second end 34 configured for mounting into a chuck or other appropriate holding device. For arrangements in which the first end 32 of the overclad tube 14 is collapsed onto the preform core rod 12 (for example, for ODD process-

es), a quartz disc 36 is positioned within the second end 34 of the overclad tube 14 to provide support for the preform core rod 12. Alternatively, for non-ODD processes, an adjustable support rod or other supporting or spacer means occupies the second end 34 of the overclad tube 14 to maintain the relative position of the preform core rod 12 and the overclad tube 14 during the collapse of the overclad tube 14 onto the preform core rod 12.

[0015] Once the preform core rod 12 is positioned as desired within the overclad tube 14, the proximal end 22 of the preform core rod 12 is sealed off, for example, by a seal 42 or other appropriate means. A vacuum or other pressure gradient then is established across the region between the preform core rod 12 and the overclad tube 14, for example, by operably coupling a vacuum source 44 to the second end 34 of the overclad tube 14. The overclad tube 14 is heated while the pressure gradient is maintained across the region between the preform core rod 12 and the overclad tube 14, thus causing the overclad tube 14 to collapse around the preform core rod 12, for example, in accordance with a conventional Rod-In-Tube (RIT) process.

[0016] Other processing variations exist for manufacturing optical fiber preforms. For example, in conventional RIT processes, the collapse of the overclad tube onto the preform core rod typically is performed while the overclad tube and the preform core rod are mounted in a vertical lathe. Alternatively, the collapse of the overclad tube on the preform core rod is performed in a draw tower furnace, which also is used to draw optical fiber from the resulting optical fiber preform. Such collapse is accomplished by inserting the preform core rod into an overclad tube and then moving the combined preform core rod and overclad tube coaxially through the draw tower furnace. This Overclad During Draw (ODD) technique causes the collapse of the overclad tube onto the preform core rod prior to the drawing of the fiber. Another processing variation includes successive RIT overclads on the same preform core rod, resulting in double overclad optical fiber preforms.

[0017] In conventional RIT arrangements, the length of the preform is approximately 50-100 centimeters (cm). However, as discussed hereinabove, preforms having greater length are manufactured, for example, by joining conventional preforms end-to-end. That is, the preforms ends to be joined are cut, ground (if necessary), polished and cleaned before being spliced together, for example, in a conventional manner.

[0018] The splice joints produced by conventional methods for joining overclad preforms end-to-end tend to be larger than approximately 2 cm in axial length. Splice joints of this size typically are undesirable since the glass viscosity at the preform splice joint varies to the extent that relatively significant variations in cladding occur when the preform splice joint portion of the preform is drawn into optical fiber. Such variations tend to reduce the quality of the glass and increase the likelihood of the fiber breaking during the draw. Often those

10

15

20

30

portions of the fiber are discarded. Also, because a 2 cm region of preform translates into approximately 4.6 kilometers (km) of optical fiber for a preform having a 60 millimeter (mm) diameter and approximately 10.2 kilometers (km) of optical fiber for a preform having a 90 millimeter (mm) diameter, it is desired that the axial length of preform splice joints be kept relatively small.

[0019] According to embodiments of the invention, a method and apparatus for making optical fiber preforms and optical fiber therefrom includes stacking a plurality of preform core rods in an overclad tube and collapsing the overclad tube around the preform core rods, for example, according to a RIT process. The multiple core rod optical fiber preform is used to draw optical fiber, for example, according to conventional fiber drawing techniques. Such techniques include, for example, ODD processes and double-overcladding or other multiple-overcladding processes.

[0020] According to embodiments of the invention, the preform core rods are stacked within the overclad tube. Because of imperfections such as air bubbles and slightly off-center alignment between stacked preform core rods, an interface therebetween, which subsequently draws into reduced quality glass, typically is less than approximately 1 mm in axial length. Such is compared with conventional arrangements having splice joints, for example, greater than approximately 2 cm in axial length. Also, unlike conventional preform splicing methods, according to embodiments of the invention, the preform core rods are stacked within an otherwise conventional overclad tube. Thus, joining interfaces occur only between the preform core rods, not the entire preform. This also tends to reduce the impact of the interfaces on the optical fiber that is drawn from the preform, compared to conventional joining techniques in which entire preforms (that is, core rods and overcladding) are spliced together.

[0021] Referring now to Fig. 2, shown is a cross-sectional view of an apparatus 50 used to make an overclad preform according to embodiments of the invention. The apparatus 50 includes a plurality of preform core rods 52 stacked within an overclad tube 54. The stacked preform core rods 52 result in one or more interfaces 56 therebetween. Once the plurality of preform core rods 52 are stacked within the overclad tube 54, a first end 58 of the overclad tube 54 is sealed off, for example, by a seal or other appropriate means, such as by partially collapsing a portion of the first end 58 of the overclad tube 54 onto one or more of the preform core rods 54. Fig. 2 shows the apparatus 50 once the overclad tube 54 has been sealed off, but prior to completely collapsing the overclad tube 54 around the plurality of preform core rods 52.

[0022] A pressure gradient is established across the region between the preform core rods 52 and the overclad tube 54, for example, by coupling a vacuum source or other suitable means to a second end 59 of the overclad tube 54. The overclad tube 54 is heated while the

pressure gradient is maintained across the region between the preform core rods 52 and the overclad tube 54 to collapse the overclad tube 54 around the preform core rods 52.

[0023] According to embodiments of the invention, two or more preform core rods 52 are cut and stacked, for example, coaxially, within the overclad tube 54. In this manner, no grinding or polishing steps are necessary. This compares favorable with conventional methods, in which ends of the preform (that is, the core rod and the overclad tube collapsed therearound) are cut, then ground, polished and cleaned before finally being spliced together end-to-end. Also, embodiments of the invention have to cut only the preform core rods, which typically have a diameter of approximately 15 mm. By comparison, conventional arrangements have to cut the preform rod and the overcladding, which collectively have a diameter of approximately 60-90 cm. Thus, in many respects, embodiments of the invention are less labor intense than conventional preform joining techniques.

[0024] As mentioned hereinabove, according to embodiments of the invention, stacking the preform core rods 52 within the overclad tube 54 results in the interfaces between ends of the stacked preform core rods being relatively small compared to splice joints of conventional arrangements. For example, according to embodiments of the invention, interfaces between the stacked preform core rods are approximately 1 mm or less, which translates into no more than approximately 230 meters (m) (for a 60 mm diameter preform) or approximately 520 m (for a 90 mm diameter preform) of optical fiber upon draw that might be of reduced quality. By comparison, conventional preform splice joints are at least approximately 2 cm, which, as discussed previously herein, translates into approximately 4.6 km of optical fiber for a preform having a 60 mm diameter and approximately 10.2 km of optical fiber for a preform having a 90 mm diameter upon draw. Thus, arrangements according to embodiments of the invention typically produce less optical fiber having reduced quality than do conventional arrangements.

[0025] Moreover, the quality of the optical fiber drawn from the joined portions of the preform core rods according to embodiments of the invention is much better than that drawn from conventional preform arrangements, for example, because conventional arrangements join the ends of entire preforms (that is, the core rod and the overclad tube). This compares with arrangements according to embodiments of the invention, which stack the ends of only the core rods (and not the overclad tube) within an overclad tube and thus have interfaces only between preform core rods. Also, because only the preform core rods have interfaces therebetween, preforms made according to embodiments of the invention are less likely to break when drawn into optical fiber than conventionally-joined preforms. Thus, according to embodiments of the invention, the preform core rod interfaces have less of an impact on reducing the overall quality of optical fiber drawn therefrom than the splice joints of conventional configurations.

[0026] According to embodiments of the invention, the preform core rods 52 typically are stacked within an overclad tube 54 that typically is longer than conventional overclad tubes (although such is not necessary). For example, it is within the scope of embodiments of the invention to stack two or more preform core rods 52 in an overclad tube 54 that has conventional length. However, in an effort to increase the length of the overclad preform, for example, for reasons previously discussed herein, the overclad tube 54 is approximately 2 meters long or even longer according to some embodiments of the invention. Such length compares with conventional overclad tubes, which typically are approximately 1 meter in length.

[0027] Embodiments of the invention provide greater flexibility in overcladding processes. For example, conventionally, a preform core rod portion that is much shorter in length than an overclad tube often is discarded rather than be overclad with a relatively expensive overclad tube that will not be fully used. However, according to embodiments of the invention, several smaller preform core rod portions are stacked within an overclad tube that has a conventional size, for example, approximately 1 m, or is even longer, for example, 2 m.

[0028] Referring now to Fig. 3, shown is an embodiment of the invention in which a pair of preform core rods 62, 63 are stacked within an overclad tube 64, prior to collapsing the overclad tube 64 therearound to make an overclad preform. The first core rod 62 is prepared for positioning in the overclad tube 64 by cutting a tip 66 off of a distal end 68 thereof and by cutting a handle portion 72 off of a proximal end 74 thereof, for example, as shown. The proximal end 74 of the prepared first core rod 62 is inserted into a first end 76 of the overclad tube 64 (for example, as shown). Alternatively, the distal end 68 of the prepared first core rod 62 is inserted into the first end 76 of the overclad tube 64.

[0029] The second core rod 63 is prepared for insertion into the overclad tube 64 by cutting a tip 78 off of a distal end 82 thereof. A handle portion 84 typically remains part of a proximal end 86 of the second core rod 63, for example, as shown. The prepared second core rod 63 is positioned within the overclad tube 64, for example, by inserting its distal end 82 into the first end 76 of the overclad tube 64 in such a way that the distal end 82 of the second core rod 63 stacks onto, for example, the distal end 68 of the first preform core rod 62. Once the preform core rods 62, 63 are stacked in the overclad tube 64, for example, as shown, the overclad tube 64 is collapsed around the preform core rods 62, 63, for example, as discussed hereinabove.

[0030] Referring now to Fig. 4, shown is a simplified block diagram of a method 90 for making overclad optical fiber preforms using multiple preform core rods, and making optical fiber therefrom. One step 92 of the meth-

od 90 is to provide an overclad tube. As discussed previously herein, the overclad tube has conventional dimensions or, alternatively, is greater in length than conventionally-sized overclad tubes.

[0031] Another step 94 is to position a plurality of preform core rods in the overclad tube. For example, the plurality of preform core rods are stacked end-to-end within the overclad tube. As discussed previously herein, according to embodiments of the invention, the stacked preform core rods have interfaces therebetween that are approximately 1 mm in axial length.

[0032] Once the plurality of preform core rods are stacked within the overclad tube, another step 95 is to seal off one end of the preform core rod stack and the overclad tube. The end is sealed, for example, by a seal or by collapsing a portion of the overclad tube onto a portion of one or more stacked preform core rods (see, for example, Fig. 2). Another step 96 is to establish a pressure gradient between the preform core rods and the overclad tube, for example, using a vacuum source or other suitable means. The pressure gradient is established such that the pressure outside of the overclad tube is greater than the pressure between the outside of the preform core rods and the inside of the overclad tube. For example, the pressure gradient is within the range from approximately 0.10 to approximately 0.50 atmospheric pressure.

[0033] Another step 98 in the method 90 is to heat the stacked preform core rods and the overclad tube, for example, within the range from approximately 1600-1700° C. According to an embodiment of the invention, the heating step 98 applies heat, for example, to successive axial portions of the combined preform core rods and overclad tube, that is, along the length of the overclad tube.

[0034] The heating step 98 causes the overclad tube to collapse onto the preform core rods stacked therein. Thus, according to embodiments of the invention, a multiple core rod optical fiber preform is formed using a stacked plurality of preform core rods and a single overclad tube, compared to conventional arrangements that splice join one or more overclad tube preforms.

[0035] Referring again to Fig. 4, another step 99 is to draw optical fiber from the heated preform. The drawing step 99 is performed, for example, in a conventional manner. That is, the drawing step 99 is performed once the inventive optical fiber preform has been manufactured. Alternatively, in an ODD-type process, the drawing step 99 is performed as the overclad optical fiber preform is being formed, that is, as the overclad tube is being collapsed onto the preform core rods within the draw tower furnace. More specifically, the heat source used to heat and collapse the overclad tube around the preform core rods is a draw tower furnace and the overclad tube with the preform core rods stacked therein is moved operably through the draw tower furnace. In this manner, the overclad tube collapses on the preform core rods using a single heat source and a single heating

35

15

20

25

30

35

40

step. The resulting multiple rod optical fiber preform then is used to draw optical fiber therefrom, for example, according to conventional ODD process steps.

[0036] It will be apparent to those skilled in the art that many changes and substitutions can be made to the embodiments of the methods and apparatus for making multiple core rod optical fiber preforms and optical fiber therefrom herein described without departing from the invention as defined by the appended claims. For example, embodiments of the invention are useful with double-overclad techniques where one or more preform core rods and a plurality of inner overclad tubes are stacked within a single, second (outer) overclad tube. Also, embodiments of the invention are useful with other multi-overclad processes, especially when the stacked preform core rods and the stacked overclad layers are stacked within a single, outermost overclad tube.

Claims

 A method (90) for making an optical fiber preform, comprising the steps of:

providing (92) at least one overclad tube; positioning a preform core rod in the overclad tube; and

heating (98) the overclad tube and preform core rod in such a way that the overclad tube collapses onto the preform core rod to form an overclad optical fiber preform,

**CHARACTERIZED IN THAT** 

the positioning step further comprises stacking (94) a plurality of preform core rods in the overclad tube, and

the heating step further comprises heating the overclad tube and the plurality of preform core rods in such a way that the overclad tube collapses onto the plurality of preform core rods to form an overclad optical fiber preform.

- The method as recited in claim 1, wherein the stacking step further comprises stacking the plurality of preform core rods within the overclad tube in such a way that the overclad tube and the plurality of preform core rods are substantially coaxial.
- 3. The method as recited in claim 1, wherein the plurality of preform core rods are stacked in such a way that an interface is formed between coupling ends of at least one pair of preform core rods, and wherein the axial length of the interface is less than approximately 1 millimeter (mm).
- The method as recited in claim I, further comprising the step of creating a pressure gradient across the


overclad tube wherein the pressure outside the overclad tube is greater than the pressure inside the overclad tube.


- The method as recited in claim 1, further comprising the step of drawing an optical fiber from the overclad optical fiber preform.
- The method as recited in claim 5, wherein the drawing step and the heating step are performed using the same heat source.
  - The method as recited in claim 1, further comprising
    the step of cutting at least one of the ends of at least
    one of the plurality of preform core rods before the
    plurality of preform core rods are stacked within the
    overclad tube.
  - 8. An apparatus for making an optical fiber preform, the apparatus comprising:

at least one overclad tube; and a plurality of preform core rods dimensioned to fit end-to-end within the overclad tube, wherein the plurality of preform core rods are stacked within the overclad tube.

- The apparatus as recited in claim 8, wherein the plurality of preform core rods are stacked within the
  overclad tube in such a way that the overclad tube
  and the plurality of preform core rods are substantially coaxial.
- 10. The apparatus as recited in claim 8, further comprising a spacer positioned within the overclad tube for supporting one of the plurality of preform core rods within the overclad tube.

6








FIG 4



# PARTIAL EUROPEAN SEARCH REPORT

Application Number

which under Rule 45 of the European Patent ConventionEP 01 30 1471 shall be considered, for the purposes of subsequent proceedings, as the European search report

	<del></del>	DERED TO BE RELEVANT		<del> </del>
Category	Citation of document with of relevant pas	indication, where appropriate, sages	Relevant to daim	CLASSIFICATION OF THI APPLICATION (INLCL7)
х	US 4 602 926 A (HAI 29 July 1986 (1986		1-9	C03B37/012
Y		6 - column 4, line 8;	10	
Y	PATENT ABSTRACTS OF vol. 12, no. 82, 15 March 1988 (1988 & JP 62 216933 A (6 24 September 1987 (* * abstract *	B-03-15) DCEAN CABLE CO LTD),	10	
x	PATENT ABSTRACTS OF vol. 6, no. 143, 3 August 1982 (1982 & JP 57 067040 A (1982 23 April 1982 (1982	2-08-03) NT&T CORP ET AL),	1,2,4,5, 8,9	
Y	* abstract *		3,7,10	
x	EP 0 737 873 A (COM 16 October 1996 (19		1-9	TECHNICAL FIELDS
Y		50 - column 22, line 7;	3	SEARCHED (Int.CL7
		-/		
INCO	APLETE SEARCH		l	
not comply be carried	h Division considers that the present with the EPC to such an extent that out; or can only be carried out partia arched completely;	application, or one or more of its claims, does a meaningful search into the state of the art cally, for these claims.	s'do annol	
Claims sea	arched incompletely:			
Claims no	searched:			
Reason to	r the timitation of the search:			
see	sheet C			
	Place of search THE HAGUE	Date of completion of the search 24 September 2001	Str	Examiner Oud, J
X : partic Y : partic docu	TEGORY OF CITED DOCUMENTS cutarty relevant if taken alone cutarty relevant if combined with another to the same category tological background	E : earlier paient doct after the filling date ther D: document cited in L : document cited for	ument, but publis e the application rother reasons	
	written disclosure	& ; member of the sa		

### EP 1 182 173 A1



## **INCOMPLETE SEARCH** SHEET C

Application Number

EP 01 30 1471

Claim(s) searched completely: 2,9

Claim(s) searched incompletely: 1,3-8,10

Reason for the limitation of the search:

Present claims 1,3-8,10 relate to an extremely large number of possible methods and preform assemblies. Support within the meaning of Article 84 EPC and disclosure within the meaning of Article 83 EPC is to be found, however, for only a very small proportion of the said methods and preform assemblies (the latter claimd as an "apparatus") claimed.

In the present case, the claims so lack support, and the application so lacks disclosure, that a meaningful search over the whole of the claimed scope is impossible.

Consequently, the search has been carried out for those parts of the claims which appear to be supported and disclosed, namely those parts relating to the method and preform assembly defined by the independent claims 1 and 8 and further limited to core-forming rods stacked end-to-end and substantially axially aligned; particular attention was given to prior art processes and preforms where no fusion splicing of the abutting rod ends was undertaken.

# EP 1 182 173 A1



# PARTIAL EUROPEAN SEARCH REPORT

Application Number

EP 01 30 1471

	DOCUMENTS CONSIDERED TO BE RELEVANT	·,	CLASSIFICATION OF THE APPLICATION (Int.CI.7)
Category	Citation of document with Indication, where appropriate, of relevant passages	Relevant to claim	
Y	PATENT ABSTRACTS OF JAPAN vol. 6, no. 214, 27 October 1982 (1982-10-27) -& JP 57 118042 A (SHOWA ELECTRIC WIRE CO LTD), 22 July 1982 (1982-07-22) * abstract; figures 3,4 *	7,10	
X	PATENT ABSTRACTS OF JAPAN vol. 6, no. 202, 13 October 1982 (1982-10-13) & JP 57 111256 A (NT&T CORP ET AL), 10 July 1982 (1982-07-10) * abstract *	1,2,4,5, 8,9	
Х	US 4 195 980 A (INTERNATIONAL STANDARD ELECTRIC CORP) 1 April 1980 (1980-04-01) * column 2, line 48 - line 62; figure 3 *	1-5,8,9	TECHNICAL FIELDS SEARCHED (Int.Ci.7)
	PATENT ABSTRACTS OF JAPAN vol. 13, no. 32, 25 January 1989 (1989-01-25) -& JP 63 231405 A (FURUKAWA ELECTRIC CO LTD), 27 September 1988 (1988-09-27) * abstract; figure 4 *	1,8	

# EP 1 182 173 A1

## ANNEX TO THE EUROPEAN SEARCH REPORT ON EUROPEAN PATENT APPLICATION NO.

EP 01 30 1471

This annex lists the patent family members relating to the patent documents cited in the above-mentioned European search report. The members are as contained in the European Patent Office EDP file on The European Patent Office is in no way liable for these particulars which are merely given for the purpose of information.

24-09-2001

US	Patent docume cited in search re		Publication date	}	Patent fa member		Publicatio date
	4602926	Α	29-07-1986	GB	2148273	. A	30-05-198
	,002520	,,		ĒΡ	0141534		15-05-198
				ES	536975		16-11-198
				ËŠ	8702313		16-03-198
				JP	60103046		07-06-198
 JP	62216933	A	24-09-1987	NONE			
JP	57067040	Α	23-04-1982	NONE		_~~	
FP	0737873	A	16-10-1996	US	5894537		13-04-1999
	0/3/0/3	- 11	10 10 1330	AU	693329		25-06-1998
				AU	5046196		24-10-1996
				BR	9601344		
					2174055		13-01-1998
				CA			14-10-1996
				CN	1165305		19-11-1997
				EP	0737873		16-10-1996
				ΕP	0949519		13-10-1999
				EΡ	0949520	A1	13-10-1999
				JP	8320419	Α	03-12-1996
				US	6044191	Α	28-03-2000
				US	6173588	<b>B</b> 1	16-01-2001
JP !	57118042	A	22-07-1982	NONE			***********
JP !	57111256	A	10-07-1982	NONE			— — — — — — — — — — — — — — — — — — —
US 4	4195980	Α	01-04-1980	GB	1551657	Α	30-08-1979
				ΑU	520411	B2	28-01-1982
				AU	3603278		15-11-1979
				CA	1106180		04-08-1981
				CH	631268		30-07-1982
				FR	2391170		
							15-12-1978
				JP	1182141	-	09-12-1983
				JP	53143342		13-12-1978
				JP NL	58012212 7805062		07-03-1983 21-11-1978
	 53231405		27-09-1988	NONE			